


7. On the CPU backplane, remove G727 bus grant card from the desired SPC slot (Figure 3-3). A bus grant (continuity) card must be in connector D of any unused SPC slot. Otherwise, bus grant continuity is lost.



NOTE
IF G7272 IS INSTALLED, IT FITS
INTO SLOTS C AND D.

MA-8785
SHR-0405-85

Figure 3-3 Bus Grant Continuity Card