

FIELD MAINTENANCE PRINT SET

TABLE OF CONTENTS

[illegible]

Digital Equipment Corporation

REVISIONS	REV.	A	B	USED ON OPTION/MODEL			DRN.	P. FAVINI	DATE	7SEP82	TITLE: 877 POWER CONTROLLER										
	CHG. NO.	INITIAL	877-ML001					CHK'D	E. MCCULLOUGH	DATE											14JAN83
	DATE	-	3/30/83					PROJ. ENG.	A. BARON	DATE											20JAN83
								FIELD SERV.	R. KLABIS	DATE	20JAN83	SIZE B	CODE TC	NUMBER 877-0-1						REV. B	
					SHEET I OF 1						DIST.										

" THIS DRAWING AND SPECIFICATIONS, HEREIN, ARE THE PROPERTY OF DIGITAL EQUIPMENT CORPORATION AND SHALL NOT BE REPRODUCED OR COPIED OR USED IN WHOLE OR IN PART AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION." COPYRIGHT © 1983


UNIT VARIATIONS

[illegible][illegible]


ML 1

TITLE: 877 POWER CONTROLLER		SHEET 2 OF 3		SIZE B DD		NUMBER 877-0-DBU0		REV. B	
-----------------------------	--	--------------	--	-----------	--	-------------------	--	--------	--

ML 1



REVISIONS		
CHG	CHANGE NO.	REV.
-	INITIAL	A
EW	B77 M 001	B
P. GAGNE 4/01/83		
A. BARN		
MM	B77 M 003	C
M. JOSEPH 15PT83		
A. BARN		



PART NO.	REV	LEGEND
877-A	C1	977-A-POWER CONTROLLER, 120V, 12A
877-B	C1	877-B-POWER CONTROLLER, 240V, 12A
877-C	C1	877-C-POWER CONTROLLER, 120V, 16A
877-D	C1	877-D-POWER CONTROLLER, 120V, 24A
877-E	C1	877-E-POWER CONTROLLER, 240V, 24A

[illegible]

CAUTION: OFF SHEET PARTS LIST
SEE K-PL-877-0-DBP.

```

LAYER #6:  FORMAT SHEETS 2 & 3
LAYER #5:  WORK SHEET 3
LAYER #4:  WORK SHEET 2
LAYER #3:  FORMAT SHEET 1
LAYER #2:  WORK SHEET 1
LAYER #1:  INFORMATION
PLOT SCALE: 1.00
SYSTEM #20
PROGRAM VERSION: UGRAF D4.0
FILE NAME: B77.0.DBUC
Z NO.: 5270
POWER CONTROLLER

```

11. LABEL "P8" USING ITEM 77.

~~0. WIRING FROM CONTROL BOARD HARNESS~~
~~3. 1. 7020657-0-000. PUT SHRINK TUBING~~
~~1111EM 701 OVER 51 CONNECTIONS~~

9. PLACE CAPACITORS C2 AND C3 (ITEMS 7 OR 10) AND MOV'S (ITEMS 8 OR 9) NO CLOSER THAN .10 INCHES FROM SIDE PANELS.

~~3. PLACE CHINA TROOPING LITEN / AT OVER
PILOT FIGHT TERMINALS AND POWER
BUS FILTER TERMINALS.~~

7. VIEWS SHOWN ARE FOR REFERENCE ONLY.
SEE WIRE TABLES AND PARTS LIST FOR
CORRECT VARIATION REQUIREMENTS.

6. LENGTHS IN WIRE TABLE ARE IN INCHES UNLESS OTHERWISE SPECIFIED. TOL $\pm .50$.

5. LEADS ON CAPACITOR ITEM 70R 101 AND VARIATOR ITEM 8 OR 91 TO BE APPROX. 1.125 IN. LONG. SEE WIRE TABLE.

~~4. TO ENSURE PROPER WIRE ALIGNMENT TO THE CONNECTOR, THE PLUG END OF THE CABLE SHOULD BE PER SECTION 4.1.~~

RELIEF.
D. 12+2 INCH LBS FOR LOCAL-REMOTE SWITCH.

CONNECTIONS ON CIRCUIT BREAKER
ICB1, OUTLETS J3-J5 ITEMS 60
OR 61, AND LAMP SOCKET.


ELECTRO-MECHANICAL CONNECTIONS:
A) 18+2 INCH LBS FOR TERMINALS
ON LINE FILTER AND GROUND STUD.

NOT COME IN CONTACT WITH THE CONTROL BOARD ON THE RIGHT SIDE PANEL.

2. THE BLU AND BRN WIRES FROM CONTACTOR (K1) TO CIRCUIT BREAKER (K2) ARE

NOTES:

NOTES:



REVISION HISTORY		
DATE	ECO HISTORY	REV

DOCUMENT NUMBER		TITLE	

AUTOMATED BY PRTLST.4Q(50)

PARTS LIST

SHEET A1 OF A2


LINE	ITEM	DOCUMENT NUMBER	PART NUMBER	DESCRIPTION	QUANTITY PER VARIATION				
					A	B	C	D	E
1	1	E-AD-7019938-0-DBU	7019938-00	FRONT PANEL ASSY. (877-A)	1	-	-	-	-
2	2	E-AD-7019938-0-DBU	7019938-01	FRONT PANEL ASSY (877-B)	-	1	-	-	-
3	3	E-AD-7019938-0-DBU	7019938-02	FRONT PANEL ASSY (877-C)	-	-	1	-	-
4	4	E-AD-7019938-0-DBU	7019938-03	FRONT PANEL ASSY (877-D)	-	-	-	1	-
5	5	E-AD-7019938-0-DBU	7019938-04	FRONT PANEL ASSY (877-E)	-	-	-	-	1
6	6	D-IA-7427397-0-DBU	7427397-01	PANEL, REAR	1	1	1	1	1
7	7	A-PS-1014430-0-0	1014430-01	.1 MFD 270V 20% M.POLYPROP	2	-	2	3	-
8	8	A-PS-1311996-0-0	1311996-00	VARISTOR 150VAC VOLT TRANS SUP	2	-	2	3	-
9	9	A-PS-1311996-0-0	1311996-02	VARISTOR 275VAC VOLT TRANS SUP	-	2	-	-	3
10	10	A-PS-1018866-0-0	1018866-00	.1 MFD 800V 20% POLYPROP	-	2	-	-	3
11	11	D-IA-7019999-0-DBU	7019999-00	PANEL, RIGHT SIDE ASSY.	1	1	1	1	1
12	12	D-MD-7427398-0-DBU	7427398-01	COVER, TOP	2	2	2	2	2
13	13	C-MD-7427396-0-DBU	7427396-01	COVER	1	1	1	1	1
14	14	A-PS-1700025-0-0	1700025-00	PWR CORDAGE 3COND 12AWG STO	1	1	1	-	-
15	15		9107548-00	PWR CORDAGE 3COND 10AWG ST	-	-	-	1	1
16	16		9008938-00	CONN, POWER 02P3W PLUG NEMA 05-1	1	-	-	-	-
17	17	A-PS-1215183-0-0	1215183-00	CONN, POWER 02P03W PLUG NEMA 05-	-	-	1	-	-
18	18		9008853-00	CONN, POWER 02P03W PLUG NEMA 06-1	-	1	-	-	-
19	19	A-PS-1211193-0-0	1211193-00	CONN, POWER 02P03W PLUG NEMA L05-	-	-	-	1	-
20	20	A-PS-1216886-0-0	1216886-00	CONN, POWER 02P03W PLUG NEMA LG -	-	-	-	-	1
21	21	A-PS-3617676-0-0	3617696-01	LABEL, DANGER HIGH VOLTAGE	1	1	1	1	1
22	22	A-PS-3613210-0-0	3613210-02	LABEL, UL FOIL ADH BACK	1	1	1	1	1
23	23		9006690-00	WASHER, HELICAL SPLIT SST	2	2	2	2	2
24	24		9000001-23	STANDOFF, MALE/FEMALE HEX 10-32	2	2	2	2	2
25	25	A-PS-3612063-0-0	3612063-00	LABEL, , ADHESIVE I.D. FOR UL C	1	1	1	1	1
26	26	A-PS-3613211-0-0	3613211-01	DECAL, CLEAR PREPRINTED CSA 1-1/4	1	1	1	1	1
27	27	A-PS-3617614-0-0	3617614-00	LABEL, CAUTION OVER CURRENT PROTE	-	-	-	1	1
28	28	A-PS-3621131-0-0	3621131-01	LABEL, 877A PWR CONTROL	1	-	-	-	-
29	29	A-PS-3621131-0-0	3621131-02	LABEL, 877B PWR CONTROL	-	1	-	-	-
30	30	A-PS-3621131-0-0	3621131-03	LABEL, 877C PWR CONTROL	-	-	1	-	-

REVISION HISTORY		BASIC PART NO: 00877		DRN: P. FAVINI		DATE: 07-OCT-82		D I G I T A L	
ENG:	ECO NUMBER	REV	SECTION A OF A	CHK'D: E. MCCULLOUGH		DATE: 21-JAN-83		TITLE PARTS LIST	
INITIAL		A	SECTION VARIATION INDEX	DES.ENG.: I. KRISHTAL		DATE: 21-JAN-83		DOCUMENT NUMBER	
A.B. 877-ML001		B	[A] A , B , C , D , E	RESP.ENG.: A. BARON		DATE: 21-JAN-83		SIZE: CODE: NUMBER	
			[B]	MFG.ENG.: R. KENNEDY		DATE: 21-JAN-83		K PL 877-0-DBP	
			[C]	ASSEMBLY NUMBER:		TOP DOCUMENT NUMBER:		FILE NAME: EDIT #	
			[D]	E-UA-877-0-DBU		#8-DD-877-0-DBU		Z5270B.PLS 21	
			[E]						
			[F]						
"THIS DRAWING AND SPECIFICATIONS HEREIN, ARE THE PROPERTY OF DIGITAL EQUIPMENT CORPORATION AND SHALL NOT BE REPRODUCED OR COPIED OR USED IN WHOLE OR IN PART AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION. COPYRIGHT (C) 1983. DIGITAL EQUIPMENT CORPORATION "									

LINE ITEM	DOCUMENT NUMBER	PART NUMBER	DESCRIPTION	A	B	C	D	E
31	A-PS-3621131-0-0	3621131-04	LABEL, 877D PWR CONTROL	-	-	-	-	1
32	A-PS-3621131-0-0	3621131-05	LABEL, 877E PWR CONTROL	-	-	-	-	1
33		9107786-66	WIRE, 18AWG(19/30)IPVC 300V1	A/R	A/R	A/R	A/R	-
34		9010439-01	NUT,CAP 6-32X 5/16AF	A/R	A/R	A/R	A/R	4
35		9107380-66	WIRE, 12AWG19/.0185IPVC 300V1	A/R	A/R	A/R	A/R	-
36		9107380-11	WIRE, 12AWG19/.0185IPVC 300V1	A/R	A/R	A/R	A/R	-
37		9010174-00	SCREW,SEMS PAN PHIL 6-	A/R	A/R	A/R	A/R	12
38		9000039-06	SCREW,MACH FLAT PHIL 4-	A/R	A/R	A/R	A/R	4
39		9006560-00	NUT,HEX EXT T00TH LCKWSHR 6-32	A/R	A/R	A/R	A/R	6
40	A-PS-1214574-0-0	1214574-02	STRAIN RELIEF,PWR CORD	A/R	A/R	A/R	A/R	1
41		9006565-00	NUT,HEX EXT T00TH LCKWSHR 10-32	A/R	A/R	A/R	A/R	4
42		9007651-00	WASHER,LOCK EXTERNAL STEEL	A/R	A/R	A/R	A/R	1
43	D-IA-7427401-0-DBU	7427401-01	PANEL,LEFT SIDE	A/R	A/R	A/R	A/R	1
44	A-PS-1214283-0-0	1214283-00	CONTRACTOR, 20A,2P	A/R	A/R	A/R	A/R	1
45	A-PS-1214283-0-0	1214283-01	CONTRACTOR, 20A,2P	A/R	A/R	A/R	A/R	1
46	A-PS-1211147-0-0	1211147-00	CONTRACTOR, 30A,3P DBL BRK,600V,1	A/R	A/R	A/R	A/R	1
47	A-PS-1211147-0-0	1211147-01	CONTRACTOR, 30A,3P DBL BRK,600V,2	A/R	A/R	A/R	A/R	1
48	D-IA-7020431-0-DBU	7020431-01	HARNESS CONTRACTOR (877-D)	A/R	A/R	A/R	A/R	1
49	D-IA-7020431-0-DBU	7020431-02	HARNESS CONTRACTOR (877-E)	A/R	A/R	A/R	A/R	1
50		9007031-00	TIE,CABLE BUNDL.DIA 0- 3/4"=101	A/R	A/R	A/R	A/R	1
51		9010174-01	SCREW,SEMS PAN PHIL 8-	A/R	A/R	A/R	A/R	4
52	A-PS-1221361-0-0	1221361-01	SCREW,CAPITIV PHIL 6-32	A/R	A/R	A/R	A/R	4
53	A-PS-1216885-0-0	1216885-01	CONN,POWER 02P05W RCPT NEMA 06-2	A/R	A/R	A/R	A/R	10
54		9007926-01	TERM,RING #10STUD CRIMP	A/R	A/R	A/R	A/R	19
55	A-PS-3612680-0-0	3612680-00	DECAL, GROUND SIGN PER 3E6 *	A/R	A/R	A/R	A/R	1
56		9107779-54	WIRE, 10AWG(105/30)IPVC 300V1	A/R	A/R	A/R	A/R	1
57		9009695-07	*** THIS ITEM IS NOT USED ***	A/R	A/R	A/R	A/R	-
58		9007970-00	TERM,QUICK .3001AB CRIMP 18-2	A/R	A/R	A/R	A/R	1
59		9009695-02	TERM,SPADE #8STUD CRIMP 10-1	A/R	A/R	A/R	A/R	6
60	A-PS-1212265-0-0	1212265-00	CONN,POWER 02P03W RCPT NEMA 05-2	A/R	A/R	A/R	A/R	3
61	A-PS-1211204-0-0	1211204-03	CONN,POWER 02P03W RCPT NEMA 06-1	A/R	A/R	A/R	A/R	0
62		9107278-09	TUBING,TEFLON .042ID	A/R	A/R	A/R	A/R	4
63		9009695-00	TERM,SPADE #8STUD CRIMP 14-1	A/R	A/R	A/R	A/R	4
64		9107390-66	WIRE, 10AWG(105/30)IPVC 300V1	A/R	A/R	A/R	A/R	-
65		9107390-11	WIRE, 10AWG(105/30)IPVC 300V1	A/R	A/R	A/R	A/R	-
66		9006999-00	TERM,RING #10STUD FLAG 16-1	A/R	A/R	A/R	A/R	0
67		9007928-00	TERM,RING #10STUD CRIMP 14-1	A/R	A/R	A/R	A/R	2
68		9007930-00	TERM,RING #10STUD CRIMP 16-2	A/R	A/R	A/R	A/R	1
69	A-PS-1212170-0-0	1212170-00	MATE-N-LOK 01SKT 20-14AWG .0850D	A/R	A/R	A/R	A/R	3
70		9107786-11	WIRE, 18AWG(19/30)IPVC 300V1	A/R	A/R	A/R	A/R	-
71	A-PS-3616073-0-0	3616073-00	LABEL,ID W/COPY VERTICAL	A/R	A/R	A/R	A/R	1
72		9006633-00	WASHER,LOCK INTERNAL STEEL	A/R	A/R	A/R	A/R	4
73		9006664-00	WASHER,FLAT SST	A/R	A/R	A/R	A/R	3
74		9107305-02	TUBING,SHRINK .187ID EXP	A/R	A/R	A/R	A/R	1
75	A-PS-1212167-0-0	1212167-01	MATE-N-LOK 04SKT(1X04).250CC HSG	A/R	A/R	A/R	A/R	1
76	A-PS-9107714-0-0	9107714-00	TUBING,SHRINK .093ID EXP	A/R	A/R	A/R	A/R	-

D	I	G	I	T	A	L	TITLE	SECTION A OF A	SIZE	CODE	DOCUMENT NUMBER	REV
							877 POWER CONTROLLER		K	PL	877-0-DBP	B

THIS DRAWING AND SPECIFICATIONS HEREBY ARE THE PROPERTY OF THE UNITED STATES GOVERNMENT AND SHALL NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION IN WRITING FROM THE UNITED STATES GOVERNMENT.



NOTE:
120V CONNECTION FOR 877-A
240V CONNECTION FOR 877-B

FOR VARIATIONS 877-A,B&C ONLY

(PLUGS AND RECEPTACLES SHOWN ARE FOR 877-A,C)

REV	INITIAL
1	A

DRN	1-0-228	FIRST USED ON	877
ENG		TITLE	POWER CONTROL (877)
PROL ENG		SIZE	D
PROD		CODE	CS 877-0-1
NEXT HIGHER ASSY		NUMBER	
SCALE	NONE	REV	A
SHEET	1 OF 2	DIST	

REVISIONS		
CHK	CHANGE NO.	REV.
—	INITIAL	A
LEM	B77 MLOOI	B
P. GAGNE 4/1/83		
A. BARON		

[illegible]

LAYER #3: FORMAT
LAYER #2: WORK
LAYER #1: INFORMATION
PLOT SCALE: 1.00
SYSTEM #20
PROGRAM VERSION: UGRAF D3.0
FILE NAME: 7019938-0-DBUA
TITLE: FRONT PANEL ASSY (8771)
Z NO.: 5214

1. REQUIRED TORQUE LEVELS:
 - A. 18±2 INCH LBS FOR TERMINALS ON LINE FILTER (ITEM 5).
 - B. 14±2 INCH LBS FOR SCREW CONNECTIONS ON CIRCUIT BREAKER CB1 (ITEM 2,3 OR 4) & LAMP MTG NUT.
 - C. 12±2 INCH LBS FOR LOCAL-REMOTE SWITCH.
2. LENGTHS GIVEN IN WIRE TABLE ARE IN INCHES. TOL ±.50.

CAUTION: OFF SHEET PARTS LIST
SEE K-PL-7019938-0-DBP.

[illegible]

SHEET A1 OF A1

QUANTITY PER VARIATION

DESCRIPTION

QUANTITY PER VARIATION

[illegible]

"THIS DRAWING AND SPECIFICATIONS HEREIN, ARE THE PROPERTY OF DIGITAL EQUIPMENT CORPORATION AND SHALL NOT BE REPRODUCED OR COPIED OR USED IN WHOLE OR IN PART AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION. COPYRIGHT (C) 1983. DIGITAL EQUIPMENT CORPORATION "






"THIS DRAWING AND SPECIFICATIONS, HEREIN, ARE THE PROPERTY OF DIGITAL EQUIPMENT CORPORATION AND SHALL NOT BE REPRODUCED OR COPIED OR USED IN WHOLE OR IN PART AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION.
COPYRIGHT © 1983 DIGITAL EQUIPMENT CORPORATION"

WIRE TABLE											
ITEM NO.	DESCRIPTION			FROM				TO			
	AWG	COLOR	POINT	CONN	STRIP	WITH		POINT	CONN	STRIP	WITH
10	22	ORG	1	FL2-1	.25	SOLDER		7	SI-1	.25	SOLDER
5		RED	2	FL2-1				16	J8-1		ITEM4
6		BLK	3	FL2-2				12	P5-2		ITEM3
6		BLK	4	FL2-2				20	J8-2		ITEM4
7		GRN	5	FL2-3				11	P5-3		ITEM3
7		GRN	6	FL2-3				22	J8-3		ITEM4
5		RED	8	SI-2				13	P5-1		ITEM3
7		GRN	9	SI-3	.25	SOLDER		10	P5-3		ITEM3
5		RED	14	J9-1		ITEM4		17	J8-1		ITEM4
6		BLK	15	J9-2		ITEM4		19	J8-2		ITEM4
7	22	GRN	16	J9-3		ITEM4		21	J8-3		ITEM4

LEGEND		
PART NO.	REV	VARIATION
7020657-01	B1	AS SHOWN

NOTES:

- USE TIE WRAPS (X) ITEM 9 APPROXIMATELY EVERY 3 INCHES WHEN NECESSARY AND AT EVERY BREAKOUT POINT.
- CONNECTORS TO BE LABELED WITH COMPONENT IDENTIFIERS ITEMS 11 & 12.
- UNLESS OTHERWISE NOTED ALL LENGTHS ARE IN INCHES.
- POSITION OF KEYING SLOT ON SWITCH BARREL DETERMINES PIN 1 (AS SHOWN).
- PLACE SHRINK TUBING (ITEM 16) OVER SWITCH TERMINALS.



LAYER #2 = FORMAT LAYER
LAYER #1 = WORK LAYER

PLOT AT: 1.00

CAUTION: OFF SHEET PARTS LIST
REFER TO K-PL-7020657-0-DBP
(Z6444)


REV.	CHANGE NO.	DATE	BY	APP.
1	1	4/07/83	P. GAGNE	
2	2	4/07/83	A. BARON	
3	3	4/07/83	M. JOSEPH	
4	4	4/07/83	A. BARON	

FIRST HIGH ABST
E-AD-7019938-0-DBU

DESCRIPTION	DRAWING NO.	PART NO.	ITEM NO.
UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND THE FOLLOWING TOLERANCES APPLY (PER DEC STD 114)			
INCHES TOLERANCES	ANGLES	APPLICABLE DIMENSION RANGE	DIMENSION RANGE IN INCHES
.015	±.01	0.000	OVER 0.000 TO 0.005
.030	±.02	0.005	OVER 0.005 TO 0.010
.060	±.03	0.010	OVER 0.010 TO 0.015
.125	±.05	0.015	OVER 0.015 TO 0.020
.250	±.07	0.020	OVER 0.020 TO 0.030
.500	±.10	0.030	OVER 0.030 TO 0.040
1.000	±.15	0.040	OVER 0.040 TO 0.050
2.000	±.20	0.050	OVER 0.050 TO 0.060
3.000	±.25	0.060	OVER 0.060 TO 0.070
4.000	±.30	0.070	OVER 0.070 TO 0.080
5.000	±.35	0.080	OVER 0.080 TO 0.090
6.000	±.40	0.090	OVER 0.090 TO 0.100
7.000	±.45	0.100	OVER 0.100 TO 0.110
8.000	±.50	0.110	OVER 0.110 TO 0.120
9.000	±.55	0.120	OVER 0.120 TO 0.130
10.000	±.60	0.130	OVER 0.130 TO 0.140
11.000	±.65	0.140	OVER 0.140 TO 0.150
12.000	±.70	0.150	OVER 0.150 TO 0.160
13.000	±.75	0.160	OVER 0.160 TO 0.170
14.000	±.80	0.170	OVER 0.170 TO 0.180
15.000	±.85	0.180	OVER 0.180 TO 0.190
16.000	±.90	0.190	OVER 0.190 TO 0.200
17.000	±.95	0.200	OVER 0.200 TO 0.210
18.000	±.1.00	0.210	OVER 0.210 TO 0.220
19.000	±.1.05	0.220	OVER 0.220 TO 0.230
20.000	±.1.10	0.230	OVER 0.230 TO 0.240
21.000	±.1.15	0.240	OVER 0.240 TO 0.250
22.000	±.1.20	0.250	OVER 0.250 TO 0.260
23.000	±.1.25	0.260	OVER 0.260 TO 0.270
24.000	±.1.30	0.270	OVER 0.270 TO 0.280
25.000	±.1.35	0.280	OVER 0.280 TO 0.290
26.000	±.1.40	0.290	OVER 0.290 TO 0.300
27.000	±.1.45	0.300	OVER 0.300 TO 0.310
28.000	±.1.50	0.310	OVER 0.310 TO 0.320
29.000	±.1.55	0.320	OVER 0.320 TO 0.330
30.000	±.1.60	0.330	OVER 0.330 TO 0.340
31.000	±.1.65	0.340	OVER 0.340 TO 0.350
32.000	±.1.70	0.350	OVER 0.350 TO 0.360
33.000	±.1.75	0.360	OVER 0.360 TO 0.370
34.000	±.1.80	0.370	OVER 0.370 TO 0.380
35.000	±.1.85	0.380	OVER 0.380 TO 0.390
36.000	±.1.90	0.390	OVER 0.390 TO 0.400
37.000	±.1.95	0.400	OVER 0.400 TO 0.410
38.000	±.2.00	0.410	OVER 0.410 TO 0.420
39.000	±.2.05	0.420	OVER 0.420 TO 0.430
40.000	±.2.10	0.430	OVER 0.430 TO 0.440
41.000	±.2.15	0.440	OVER 0.440 TO 0.450
42.000	±.2.20	0.450	OVER 0.450 TO 0.460
43.000	±.2.25	0.460	OVER 0.460 TO 0.470
44.000	±.2.30	0.470	OVER 0.470 TO 0.480
45.000	±.2.35	0.480	OVER 0.480 TO 0.490
46.000	±.2.40	0.490	OVER 0.490 TO 0.500
47.000	±.2.45	0.500	OVER 0.500 TO 0.510
48.000	±.2.50	0.510	OVER 0.510 TO 0.520
49.000	±.2.55	0.520	OVER 0.520 TO 0.530
50.000	±.2.60	0.530	OVER 0.530 TO 0.540
51.000	±.2.65	0.540	OVER 0.540 TO 0.550
52.000	±.2.70	0.550	OVER 0.550 TO 0.560
53.000	±.2.75	0.560	OVER 0.560 TO 0.570
54.000	±.2.80	0.570	OVER 0.570 TO 0.580
55.000	±.2.85	0.580	OVER 0.580 TO 0.590
56.000	±.2.90	0.590	OVER 0.590 TO 0.600
57.000	±.2.95	0.600	OVER 0.600 TO 0.610
58.000	±.3.00	0.610	OVER 0.610 TO 0.620
59.000	±.3.05	0.620	OVER 0.620 TO 0.630
60.000	±.3.10	0.630	OVER 0.630 TO 0.640
61.000	±.3.15	0.640	OVER 0.640 TO 0.650
62.000	±.3.20	0.650	OVER 0.650 TO 0.660
63.000	±.3.25	0.660	OVER 0.660 TO 0.670
64.000	±.3.30	0.670	OVER 0.670 TO 0.680
65.000	±.3.35	0.680	OVER 0.680 TO 0.690
66.000	±.3.40	0.690	OVER 0.690 TO 0.700
67.000	±.3.45	0.700	OVER 0.700 TO 0.710
68.000	±.3.50	0.710	OVER 0.710 TO 0.720
69.000	±.3.55	0.720	OVER 0.720 TO 0.730
70.000	±.3.60	0.730	OVER 0.730 TO 0.740
71.000	±.3.65	0.740	OVER 0.740 TO 0.750
72.000	±.3.70	0.750	OVER 0.750 TO 0.760
73.000	±.3.75	0.760	OVER 0.760 TO 0.770
74.000	±.3.80	0.770	OVER 0.770 TO 0.780
75.000	±.3.85	0.780	OVER 0.780 TO 0.790
76.000	±.3.90	0.790	OVER 0.790 TO 0.800
77.000	±.3.95	0.800	OVER 0.800 TO 0.810
78.000	±.4.00	0.810	OVER 0.810 TO 0.820
79.000	±.4.05	0.820	OVER 0.820 TO 0.830
80.000	±.4.10	0.830	OVER 0.830 TO 0.840
81.000	±.4.15	0.840	OVER 0.840 TO 0.850
82.000	±.4.20	0.850	OVER 0.850 TO 0.860
83.000	±.4.25	0.860	OVER 0.860 TO 0.870
84.000	±.4.30	0.870	OVER 0.870 TO 0.880
85.000	±.4.35	0.880	OVER 0.880 TO 0.890
86.000	±.4.40	0.890	OVER 0.890 TO 0.900
87.000	±.4.45	0.900	OVER 0.900 TO 0.910
88.000	±.4.50	0.910	OVER 0.910 TO 0.920
89.000	±.4.55	0.920	OVER 0.920 TO 0.930
90.000	±.4.60	0.930	OVER 0.930 TO 0.940
91.000	±.4.65	0.940	OVER 0.940 TO 0.950
92.000	±.4.70	0.950	OVER 0.950 TO 0.960
93.000	±.4.75	0.960	OVER 0.960 TO 0.970
94.000	±.4.80	0.970	OVER 0.970 TO 0.980
95.000	±.4.85	0.980	OVER 0.980 TO 0.990
96.000	±.4.90	0.990	OVER 0.990 TO 1.000
97.000	±.4.95	1.000	OVER 1.000 TO 1.010
98.000	±.5.00	1.010	OVER 1.010 TO 1.020
99.000	±.5.05	1.020	OVER 1.020 TO 1.030
100.000	±.5.10	1.030	OVER 1.030 TO 1.040
101.000	±.5.15	1.040	OVER 1.040 TO 1.050
102.000	±.5.20	1.050	OVER 1.050 TO 1.060
103.000	±.5.25	1.060	OVER 1.060 TO 1.070
104.000	±.5.30	1.070	OVER 1.070 TO 1.080
105.000	±.5.35	1.080	OVER 1.080 TO 1.090
106.000	±.5.40	1.090	OVER 1.090 TO 1.100
107.000	±.5.45	1.100	OVER 1.100 TO 1.110
108.000	±.5.50	1.110	OVER 1.110 TO 1.120
109.000	±.5.55	1.120	OVER 1.120 TO 1.130
110.000	±.5.60	1.130	OVER 1.130 TO 1.140
111.000	±.5.65	1.140	OVER 1.140 TO 1.150
112.000	±.5.70	1.150	OVER 1.150 TO 1.160
113.000	±.5.75	1.160	OVER 1.160 TO 1.170
114.000	±.5.80	1.170	OVER 1.170 TO 1.180
115.000	±.5.85	1.180	OVER 1.180 TO 1.190
116.000	±.5.90	1.190	OVER 1.190 TO 1.200
117.000	±.5.95	1.200	OVER 1.200 TO 1.210
118.000	±.6.00	1.210	OVER 1.210 TO 1.220
119.000	±.6.05	1.220	OVER 1.220 TO 1.230
120.000	±.6.10	1.230	OVER 1.230 TO 1.240
121.000	±.6.15	1.240	OVER 1.240 TO 1.250
122.000	±.6.20	1.250	OVER 1.250 TO 1.260
123.000	±.6.25	1.260	OVER 1.260 TO 1.270
124.000	±.6.30	1.270	OVER 1.270 TO 1.280
125.000	±.6.35	1.280	OVER 1.280 TO 1.290
126.000	±.6.40	1.290	OVER 1.290 TO 1.300
127.000	±.6.45	1.300	OVER 1.300 TO 1.310
128.000	±.6.50	1.310	OVER 1.310 TO 1.320
129.000	±.6.55	1.320	OVER 1.320 TO 1.330
130.000	±.6.60	1.330	OVER 1.330 TO 1.340
131.000	±.6.65	1.340	OVER 1.340 TO 1.350
132.000	±.6.70	1.350	OVER 1.350 TO 1.360
133.000	±.6.75	1.360	OVER 1.360 TO 1.370
134.000	±.6.80	1.370	OVER 1.370 TO 1.380
135.000	±.6.85	1.380	OVER 1.380 TO 1.390
136.000	±.6.90	1.390	OVER 1.390 TO 1.400
137.000	±.6.95	1.400	OVER 1.400 TO 1.410
138.000	±.7.00	1.410	OVER 1.410 TO 1.420
139.000	±.7.05	1.420	OVER 1.420 TO 1.430
140.000	±.7.10	1.430	OVER 1.430 TO 1.440
141.000	±.7.15	1.440	OVER 1.440 TO 1.450
142.000	±.7.20	1.450	OVER 1.450 TO 1.460
143.000	±.7.25	1.460	OVER 1.460 TO 1.470
144.000	±.7.30	1.470	OVER 1.470 TO 1.480
145.000	±.7.35	1.480	OVER 1.480 TO 1.490
146.000	±.7.40	1.490	OVER 1.490 TO 1.500
147.000	±.7.45	1.500	OVER 1.500 TO 1.510
148.000	±.7.50	1.510	OVER 1.510 TO 1.520
149.000	±.7.55	1.520	OVER 1.520 TO

A

1



AUTOMATED BY PRLST.4Q(50)

PARTS LIST

QTY PER VARIATION 00
REFERENCE DESIGNATOR
SHEET 01 OF 01


1	1	5015689-00
2	2	1000080-00
3	3	1018866-01
4	4	1105796-00
5	5	1212297-01
6	6	1218087-00
7	7	1301969-00
8	8	1621344-01
9	9	1300271-00
10	10	1212297-03
11	11	11110856-00
12	12	1510705-00
13	13	1518101-00
14	14	1321151-01
15	15	1300447-00
16	16	1300228-00
17	17	1316506-00
18	18	9107796-55
19	19	9107400-54
20	20	9007930-00

21 NOTE: CUT ITEM 18 APPROX 1 1/2" LONG

REVISION HISTORY										BASIC PART NO: 5415690									
ENG: ECO NUMBER										SECTION A OF A									
REV										SECTION, VARIATION INDEX									
INITIAL										CHK'D: D. BARRIERE									
A: 5415690-ML001										DATE: 08-NOV-82									
B										DES. ENG: A. BARON									
[A] 00										DATE: 08-NOV-82									
[B]										RESP. ENG: A. BARON									
[C]										MFG. ENG: B. KENNEDY									
[D]										DATE: 08-NOV-82									
[E]										TOP DOCUMENT NUMBER: B-DD-5415690-0-0									
[F]										FILE NAME: Z58498.PLS									
[G]										REV									
[H]										DOCUMENT NUMBER									
[J]										SIZE: CODE NUMBER									
[K]										PL									
[L]										5415690-0-DBP									
[M]										B									
[N]										EDIT #									
4										4									

"THIS DRAWING AND SPECIFICATIONS HEREIN, ARE THE PROPERTY OF DIGITAL EQUIPMENT CORPORATION AND SHALL NOT BE REPRODUCED OR COPIED OR USED IN WHOLE OR IN PART AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION. COPYRIGHT (C) 1983. DIGITAL EQUIPMENT CORPORATION "

THIS DRAWING AND SPECIFICATIONS HEREIN ARE THE PROPERTY OF DIGITAL EQUIPMENT CORPORATION AND SHALL NOT BE REPRODUCED OR COPIED OR USED IN WHOLE OR IN PART AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION.
COPYRIGHT © 1982
DIGITAL EQUIPMENT CORPORATION



NOTE :

1. UNLESS NOTED ALL RESISTORS ARE 1/4W, 5%

REVISION HISTORY		
DATE	ECO NUMBER	REV
04/25/00	545600 ML001	B
S. D'Ample		5/25/03
AL BARON		

ORIG	<i>S. Angeles</i>	DATE	<i>3 DEC 82</i>	TITLE digital
CHRGD	<i>G. Baron</i>	DATE	<i>3 DEC 82</i>	
ORIG ORG	<i>G. Baron</i>	DATE	<i>3-1-83</i>	
RESP ORG	<i>G. Baron</i>	DATE	<i>3-1-83</i>	
DOCUMENT NUMBER				
FILE NO.	<i>G. Baron</i>	DATE	<i>4-15-83</i>	RCR CODE NUMBER D CS 5415690-0-1 B
BEST NUMBER DOC				
82-DD-5415690-0-0				

DIGITAL EQUIPMENT CORPORATION
MAYNARD, MASSACHUSETTS

ENGINEERING SPECIFICATION

digital CONTINUATION SHEET

ENGINEERING SPECIFICATION - 877
TITLE: POWER CONTROLLER SPECIFICATION - 877
DATE: 13 JANUARY 1983

REVISIONS

REV	DESCRIPTION	CHG NO	ORIG	DATE	APPD BY	DATE
A	INIT RELEASE					
B	Doc. Change	877-ME002		5/26/83		

1.0	GENERAL DESCRIPTION
2.0	APPLICABLE DOCUMENTS
3.0	ELECTRICAL DESCRIPTION
4.0	INPUT OVERVOLTAGE SURGE RATING & CIRCUIT BREAKER RATING
5.0	POWER CONTROL BUS
7.0	RIDE THROUGH CAPABILITY
8.0	MECHANICAL AND ENVIRONMENTAL SPEC
9.0	PRODUCT SAFETY
10.0	RELIABILITY

This document contains confidential and proprietary information to Digital. This information shall not be disclosed to persons outside the employ of DEC, except by DEC personnel so authorized by DEC, and only for use by such persons in the design, production or manufacture of products for DEC.
Copyright (c) 1983 Digital Equipment Corporation.

APPD	SIZE	CODE	NUMBER	REV
A. BARON	A	SP	1877-0-2	B
A. Baron	C. Baron			

SHEET 1 OF 9

ENGINEERING SPECIFICATION digital CONTINUATION SHEET

1.0 GENERAL DESCRIPTION

1.1 MECHANICAL

The 877 power controller consists of five variations: 877-A, B, C, D and E. All have two switched duplex outlets and one unswitched duplex outlet (total of 6 outlets). All variations include an ac line filter. The 877's application is to distribute and control ac power in cabinets. All variations include a line cord and a suitable connector.

2.0 APPLICABLE DOCUMENTS

DEC STD. 002	AC Power Wiring, Grounding, Receptacles Rev. C
DEC STD. 102	Environmental Standard Rev. D
DEC STD. 122	AC Power Line Standard Rev. D
DEC STD. 123	Power Control Bus Standard Rev. A
DEC STD. 119	Product Safety Standard Rev. D

3.0 ELECTRICAL

The power controller serves four functions:

- To control large amounts of power with low signal power.
- To provide a convenient ac power distribution point.
- To disconnect power for servicing and in case of overload.

A block diagram of the basic power controller is shown in Figure

There are five (5) configurations of the power controller listed, all are single phase (see table 1).

SIZE	CODE	NUMBER	REV
A	SP	877-0-2	B

SHEET 3 OF 9

TABLE OF CONTENTS

APPD	SIZE	CODE	NUMBER	REV
A	A	SP	1877-0-2	B

SHEET 2 OF 9

ENGINEERING SPECIFICATION digital CONTINUATION SHEET

877	RATED	INPUT	RANGE	CURRENT	(PEAK I)	INPUT VA BREAKER	FULL LOAD RATING	AVG	PLUG	REMA	RECEPT.	OUTPUT
E	240	180-264	24A	500A	5760	22-20-30A	#10	16-30P	6-20R			
D	120	90-132	24A	500A	2880	22-22-30A	#10	15-30P	5-20R			
C	120	90-132	16A	400A	1920	22-22A	#12	5-20P	5-20R			
B	240	180-264	12A	300A	2880	15-15A	#12	6-15P	6-20R			
A	120	90-132	12A	300A	1440	15-15A	#12	5-15P	5-20R			

ELECTRICAL SPECIFICATIONS All values are rms unless otherwise specified.

GENERAL SPECIFICATIONS - All versions
Input and output connections are single phase 2 wire plus ground
Frequency range is 47 Hertz to 63 Hertz
Input power at no load - 10 Watts maximum
Line Filter - See A-PS-12-13070-0-0
Leakage current contribution of the Power Controller - 1.5mA max @ 250 V 60 Hz
Output Voltage - Same as input less voltage drop through unit not to exceed 2 volts

SIZE	CODE	NUMBER	REV
A	SP	1877-0-2	B

SHEET 4 OF 9

4.0 INPUT OVERVOLTAGE SURGE FOR THE POWER CONTROLLER ALONE

VERSION	PHASE TO NEUTRAL
877-A,C,D	150V, 1 SECOND
877-B,E	300V, 1 SECOND

CIRCUIT BREAKER TRIP CHARACTERISTICS

VERSIONS	DEC PART NUMBER	DELAY CURVE
877-A,B	1212124-0-8	FIG. II
877-C	1212124-0-7	FIG. II
877-D,E	1211196-0-4	FIG. III

5.0 POWER CONTROL BUS

The power control bus consists of two parallel connected three pin Mate-N-Lok connectors going to the control board. Each of these connectors feeds two three pin Mate-N-Lok connectors mounted on the power controller. The pin connections are as follows:

Pin 1 Power Request
Pin 2 Power Inhibit
Pin 3 Return

The two Mate-N-Lok connectors on the front panel are part of a power bus filter designed to reduce noise appearing at the front panel power bus Mate-N-Lok connectors.

Input signal current levels:

High $\leq 20 \mu A$
Low $\geq 20 mA$

* For worst case line voltage.

Input signal voltage levels:

High $\leq 35V$ at 132V line voltage
Low $\geq 1.6V$

6.0 LOADS

No loads external to the cabinet are to be plugged into the power controller.

SIZE	CODE	NUMBER	REV
A	SP	877-0-2	B

SHEET 5 OF 9




FIGURE I

SIZE	CODE	NUMBER	REV
A	SP	877-0-2	B

SHEET 7 OF 9

7.0 RIDE THROUGH CAPABILITY

Less than 1 millisecond.

8.0 MECHANICAL AND ENVIRONMENTAL

8.1 DIMENSIONS

6 9/16 (16.7cm) x 11 1/16 (28.1cm) x 5 5/16 (12.5cm)

8.2 WEIGHT

15 lbs. (6.8kg) max.

8.3 APPLICATION

To be used only in H640 cabinet series with H9544-S series bulkhead panels in which the outlet receptacles will not be operator accessible.

8.4 TEMPERATURE

Per DEC STD.102 Rev. C DEC Class B (10°C to 40°C) OPERATING (-40°C to 65°C) STORAGE

9.5 RELATIVE HUMIDITY

Per DEC STD.102 Rev. C DEC Class B

8.6 VIBRATION

Per DEC STD.102 REV. C DEC Class C.

8.7 SHOCK

Per DEC STD.102 Paragraph 2.0

8.8 ALTITUDE

Per DEC STD.102 Paragraph 3.0

8.9 COOLING

Convection cooled.

9.0 PRODUCT SAFETY


The 877 power controller shall conform to DEC STD.119 (Product Safety).

10.0 PRODUCT RELIABILITY

The MCBF of the 877 power controller shall be 2500. Based on one ON/OFF cycle per day (24 hours/cycle), this relates to an MTBF of 60,000 hours.

SIZE	CODE	NUMBER	REV
A	SP	877-0-2	B

SHEET 6 OF 9



TIME-DELAY CURVE

FIG. II


SIZE	CODE	NUMBER	REV
A	SP	877-0-2	B

SHEET 8 OF 9

REV	NUMBER	SIZE	CODE	SP	A
B	877-0-2				

SHEET 9 OF 9

FIGURE III
TIME-DELAY CURVE



ENGINEERING SPECIFICATION Digital CONTINUATION SHEET